



CARPET PROJECTS 2019

IFB #19-701-002

Addendum 1.0

ISSUE DATE: April 9th, 2019

Clarifications from the Pre-Bid Meeting:

- Measurement for the East entry way at Laurel is 9ft x 30ft that requires new walk-off matting to be supplied and installed with this bid.
- Inlaid walk-off mats shall be included in bid to be provided and installed by the Contractor at each exterior door where carpet is being replaced.
- All stairs that are part of the projects shall be carpet tile for the tread with rubber nose and rubber base for the riser.
- No carpet shall be installed in the staff restrooms adjacent tot room 503 at the Laurel site.
- At the Riffenburgh site, add room 200D
- At the Riffenburgh site, rooms 400A, 400B, 400D and 400F are already complete and should be removed from the bid
- At the Bauder site, the incorrect room is shown on the map. The correct room is room 6. This is the only room at this site and will require vinyl flooring to replace the vinyl flooring that is already installed, and carpet to be installed where carpet now exists.