

ADDENDUM NO. 2

South Bus Maintenance Addition

6425 Portner Road
Fort Collins CO
Project No. 1915

alm2s

712 Whalers Way, Suite B-100
Fort Collins, CO 80525
(970) 223-1820

Date April 18, 2019

To all proposed Bidders for the above-referenced project, the following changes are hereby made and will become a part of the Contract Documents:

SPECIFICATIONS

1. Section 08 71 00 COMERCIAL FINISH HARDWARE
General, Finish Hardware will be owner Furnished Contractor installed.

DRAWINGS

1. Keynote 11.05 see below for addition requirements for contractor furnished and install air compressor and filters. For Quincy QP-10 Reciprocating Air Compressor

Item	Product Description	Qty
1	QP-10 Reciprocating Air Compressor	1
	Two Stage Piston Compressor	
	Package: MAX Configured	
	Rated for 35 ACFM at 175 PSIG	
	Voltage: 230/3/60	
	Tank Size: Vertical 120	
	Unit Configuration: Simplex	
	Applications up to 175 PSIG	
	Motor Overload Protection	
	Ball Valve Tank Drain	
	Control Mode: Start/Stop	
	Industry Leading Pump Life over 60,000 Hours!	
	ODP Slow Speed Motor	
	NO BULL Warranty- Purchase EWK and get a 2 year package and 3 year pump warranty	
2	2022163613 - EWK-7 QP-10 Pro/Max Maint Kit-No Bull Warranty	1

Item	Product Description	Qty
1	QMF 50 Compressed Air Filter	1
	Pressure Indicator	
	Max Pressure (PSIG): 232	
	Die Cast Aluminum Housing	
	ISO Quality	
	Automatic Drain	
2	QWS 85B Compressed Air Filter	1
	Alochrom Treatment Corrosion Protection	
	High Nitrile Seals and Diecast Aluminum Housing	
	Float Drain connection: 0.25 inch	
	Manual Drain Connection: 0.5 inch	
3	146395 - DRAIN,FLOAT,CONDENSATE	1

ATTACHMENTS
Soils Report

END OF ADDENDUM

Receipt of this addendum must be acknowledged with the bid.

