

## Questions & Answers - 2

**Solicitation** 19-701-006 - 2019 Gym Floor Projects  
**Buying Organization** Poudre School District

No	Question/Answer	Question Date
Q2	<p><b>Question: Scope of Work</b>            Can you please tell me if the current floors are getting removed and replaced with tile or resurfaces as per exhibit A?</p> <p><b>Answer:</b> The current gym floors will need to be removed and new tiles installed.</p>	06/04/2019
Q3	<p><b>Question: Mercury Testing</b>            Have the (3) existing gym floors been tested for mercury? If so, did any of the (3) floors test positive for mercury?</p> <p><b>Answer:</b> Yes, all (3) gym floors have been tested for mercury. None of the (3) floors on this bid tested positive for mercury.</p>	06/06/2019
Q4	<p><b>Question: Court Markings</b>            Does the District prefer the new court markings to match the existing? Are lines versus filling in the keys and circles preferred? Are solid keys/circles acceptable?</p> <p><b>Answer:</b> Yes, the District prefers the new court markings match the existing markings. Solid keys/circles are acceptable.</p>	06/06/2019
Q5	<p><b>Question: Equivalent Products</b>            If our company will be providing a bid for an equivalent product, what information on the product should be included?</p> <p><b>Answer:</b> Vendors interested in proposing an equivalent gym floor product shall provide at minimum the following information with their bid response:</p> <ol style="list-style-type: none"> <li>1) Product information and specifications on the proposed product</li> <li>2) Cleaning information and specifications on the proposed product</li> <li>3) Warranty information on the proposed product</li> <li>4) References in the Front Range area who are currently using the proposed product</li> </ol>	06/06/2019
Q6	<p><b>Question: Moisture Testing</b>            Is moisture testing required for the (3) sites? If so, is this to be conducted by the District or the awarded contractor(s) and who is responsible for the cost?</p> <p><b>Answer:</b> Yes, moisture testing is required for the (3) sites. The awarded contractor(s) are responsible for the testing and any costs associated with the testing. The awarded contractor(s) will provide the District with a copy of the moisture readings, upon completion.</p>	06/06/2019
Q7	<p><b>Question: Volleyball Caps and Insert Plates</b>            Will volleyball caps and insert plates have to be lowered for all sites?</p> <p><b>Answer:</b> Yes, the volleyball caps and insert plates will need to be lowered on all floors.</p>	06/06/2019

No	Question/Answer	Question Date
Q8	<p><b>Question: Werner Timeline</b></p> <p>Given the timeline for the Werner floor includes 2 holidays, does the District have any flexibility with this timeline or is it set as is?</p> <p><b>Answer:</b> The timeline for this project is set as is.</p>	06/06/2019