

Questions & Answers - 1

Project 20-220-001 - Boltz Middle School Tubular Daylight Device Installation
Buying Organization Poudre School District

No	Question/Answer	Question Date
Q1	<p>Question: Parts and supplies What will the awarded contractor need to supply?</p> <p>Answer: Contractor will provide all parts and supplies necessary to complete the work.</p>	02/18/2020
Q2	<p>Question: Device placement Where should the devices be positioned in each classroom.</p> <p>Answer: While placement of each device may vary per classroom, they should generally have two toward the front of the room to the sides (avoid being near the screens or smart boards) and one toward the middle rear of the room.</p>	02/18/2020
Q3	<p>Question: Trim and panel What should the trim and ceiling panel look like?</p> <p>Answer: Trim and panel should look similar to the two already installed in room eight.</p>	02/18/2020
Q4	<p>Question: Roof Warranty What is the roof warranty/requirements for sealing at penetrations?</p> <p>Answer: The Boltz MS built up roof is still under warranty until 8/24 and Johns Manville certified installers must be used for repairs.</p> <ul style="list-style-type: none">B and M RoofingColorado Moisture ControlFront Range RoofingUnited Roofing	02/18/2020
Q5	<p>Question: map of rooms Do you have a map of the rooms to be affected?</p> <p>Answer: Along with this addendum is an attachment showing the rooms that were discussed during the site visit.</p>	02/18/2020