



## POUDRE SCHOOL DISTRICT R-1

IFB #21-700-002

### BUILDING AUTOMATION SYSTEMS REPLACEMENTS BLEVINS MIDDLE SCHOOL POUDRE HIGH SCHOOL

#### Addendum 3.0

**ADDENDUM POSTING DATE:** November 2, 2020

**IFB CLOSING DATE:** November 6, 2020, 2:00 p.m. MST

Notes from Site Visits

Required	Blevins	PHS
Bid shall be based on existing equipment with changes once new equipment is planned from separate solicitation.	Yes	
New wiring shall be used for all new controls	Yes	Yes
Safety Switches to be hard wired	Yes	No
Separate controls for Boiler supply and return Separate controls for Building supply and return	Yes	Yes
Glycol feeder to be alarmed	Yes	Yes
Temp sensor required for boiler room temperature with cold alarm	Yes	Yes
All exhaust fans that are switched (DDC), not alarmed (status, cmd)	Yes	Yes
All new actuators required	Yes	Yes
Building freeze alarm required	Yes	Yes
Replace existing wire mold to thermostats and use wire mold to new thermostats	Yes	Yes
Where existing controls are removed cover with plate	Yes	Yes
Site Audit after award will determine locations for panels	Yes	Yes
Any controls in RTUs shall be replaced with inside building controls	Yes	Yes
Baseball field lights shall be IP controlled		Yes
Controls in five modulars included		Yes
Terminal VAV valves shall be replaced		Yes
Units that are abandoned in place shall remain abandoned		Yes
Gas Range and hood in commercial kitchen is not included in this project		Yes