

Questions & Answers - 1

Project 21-700-002 - Building Automation Systems Replacements
Buying Organization Poudre School District

No	Question/Answer	Question Date
Q1	<p>Question: Blevins-CUH's On the walk through, there was a discussion on controlling the entry way CUH's. Please provide additional clarification on if they are to be on the BAS or if they will be stand alone</p> <p>Answer: Replace with low voltage controls of CUH</p>	11/02/2020
Q2	<p>Question: Control Panel Power Is the TC contractor responsible for providing 120VAC power to the control panels?</p> <p>Answer: Yes, TCC is responsible for Electrical sub</p>	11/02/2020
Q3	<p>Question: Blevins & PHS- TC Valves and actuator replacements On the walk through, there was a discussion on replacing both the valves and actuators on the smaller BB and VAV's and only replacing the actuators on the larger valves. Please confirm this is the correct scope on both schools for bidding purposes.</p> <p>Answer: Valve replacement is required for cartridge valves of terminal devices, entire actuator replacement is required on entire building</p>	11/02/2020
Q4	<p>Question: Communication Protocol Is the preferred communication protocol BACnet IP?</p> <p>Answer: Yes, that is correct.</p>	11/02/2020
Q5	<p>Question: Control Devices Are all control devices including wiring to be replaced?</p> <p>Answer: Yes, complete controls replacement is required, including wiring, relays, sensors, actuators and panel enclosures</p>	11/02/2020
Q6	<p>Question: PHS Control Valves Is the TC contractor responsible for replacing all of the terminal control valves at PHS?</p> <p>Answer: Yes, the TCC is responsible for this. Using the PSD plumbing specs.</p>	11/02/2020
Q7	<p>Question: PHS Roof Mounted AHU/RTU Controllers Please define which Roof mounted RTU's/AHU's currently have the BAS controllers mounted in the units on the roof that will require the new BAS controllers to be installed in panels in the building below the ceiling.</p> <p>Answer: RTUs: 1,2,3,4,5,6,7,8</p>	11/02/2020