



POUDRE SCHOOL DISTRICT R-1

IFB #22-701-003

DISTRICT ABATEMENT PROJECTS

Addendum 1.0

ADDENDUM POSTING DATE: December 7, 2021

IFB CLOSING DATE: **December 9, 2020, 2:00 p.m. MT**

The language in the solicitation shall be replaced with the following update to Section 5.9:

- 5.9 All chemicals used for abatement shall be properly removed after process to insure there will be no issues with new flooring adhesives.
 - 5.9.1 Contractor shall run a floor scrubber with bristle bushes and a chemical neutral cleaner over the entire slab to properly neutralize any chemicals used in abatement process.
 - 5.9.2 Contractor shall then perform a quick grind of the entire slab using floor buffers and 20 grit concrete grinding disk.
 - 5.9.3 Contractor shall then clean concrete dust off of the entire slab using a vacuum or floor scrubber to ensure all areas are properly prepped for new floor coverings after chemical abatement procedures have been performed.