

Questions & Answers - 1

Project 23-340-003 - Fenced Concrete Pad Project
Buying Organization Poudre School District

No	Question/Answer	Question Date
Q1	<p>Question: Gate Detail Please provide a gate detail for the 6 Foot Chain Link Fence.</p> <p>Answer: Please see the attached detail.</p>	10/21/2022
Q2	<p>Question: Irrigation Main Line What is the size of the Mainline</p> <p>Answer: The main line is class 200 PVC Pipe 3-inch size.</p>	10/27/2022
Q3	<p>Question: Slab Grade Will the new concrete slab match existing grade or will it need to be ADA compliant.</p> <p>Answer: The new concrete slab should match the existing grade on all four sides.</p>	10/27/2022
Q4	<p>Question: Schedule of Work When will this work be performed</p> <p>Answer: This work may be performed any time after the contract has been completed and PO has been issued and must be completed no later than July 31, 2023. If this work is scheduled while school is in session, we must coordinate the project with the main office. If this work is done prior to the irrigation system being charged, the mainline and all irrigation work must be pressure tested to a minimum 150 psi. prior to the concrete installation.</p>	10/27/2022
Q5	<p>Question: Winter Weather Protection Will we need to provide for winter weather protection</p> <p>Answer: Yes, all winter weather protection must be provided by the awarded contractor. The contractor must also provide all materials such as temporary orange fencing, caution tape, cones, etc to secure the construction site during construction.</p>	10/27/2022
Q6	<p>Question: Concrete Connection to Existing Will we need to drill and dowel to existing concrete or building</p> <p>Answer: Yes, the new slab must be drilled and doweled to the existing concrete slab and to the building.</p>	10/27/2022
Q7	<p>Question: Irrigation Main Line Do we need to reroute mainline or just sleeve in place</p> <p>Answer: The mainline does not need to be rerouted. It can either be sleeved in place with a 6" PVC sleeve, or it may be replaced with an HDPE mainline pipe which does not require a sleeve.</p>	10/27/2022

No	Question/Answer	Question Date
Q8	<p>Question: Slab Grade</p> <p>With no drainage called for; Is it fair to assume the slab should match the existing concrete and shed water toward the parking lot?</p> <p>Answer: Yes, this is correct. The Slab should match the existing concrete and shed water toward the parking lot.</p>	10/27/2022